West Alpha

For further information contact:

Marketing - Contract
Phone: +47 51 30 90 00
E-mail: business.development@seadrill.com
www.seadrill.com

Design	Ultra Yatzy
Built/year	NKK/1986
Modified	1991/1996/1999/2002/2004/2009
Registration	Panama
Classification	Column Stabilised Drilling Unit, UKVS, HELDK, CRANE, F-AM, POSMOOR ATA, DRILL (N)
Length o.a.	89 m
Breadth	66 m
Water depth	60 - 600 m
Drilling depth	7,000 m
Variable load	4,700 mT
Propulsion	4 x 2,450 (BHP)
Prime movers	17,500 (BHP)
Cranes	2 x National Oilwell OSE 3500, 70 mT at 17.5 m and 17 mT at 47.5 m
Mooring	8 x 15 mT Stevepris 8 x 76 mm 2,000 m chain
Derrick	MH 174 - 1.3 mill lbs
Travelling block	MH 1068 - 650 sht.
Drawworks	Wirth GH 3000 E
Topdrive	MH DDM 650-C-DC-500 S
Rotary table	Wirth RTSS 49.5" Hydraulic driven
BOP	Cameron T BOP 18 3/4" - 15k
BOP control system	Cameron, Pilot hydraulic system - 3000 psi WP
Marine riser	Vetco 1,000,000 lbs - 600 m
Riser tensioners	12 x ASMH 80,000 lbs
Heave compensators	ASMH CBC-270-20, 20 ft stroke
Active heave compensator	ASMH
Mud pumps	3 x Wirth TPK 7" x 12"/ 1,600 HP triplex
Shale shakers	6 Thule VSM 300
Drillpipe	6,000 m of 5" x 25.6 lb/ft S-135 6,000 m of 5 7/8" x 24.1 lb/ft S-135
Mud cement bulk	674 m3
Liquid mud	1,100 m3 incl. OBM 470 m3
Base oil	390 m3
Brine	700 m3
Helideck	Sikorsky S-92
Accomodation	110 persons

Third party equipment